

TENDER DOCUMENT

(NIT No. : RGNUL/CMW/09)

Dated : 15/07/2016

**PROVIDING & FIXING OF THE CUT PILE
DESIGNED CARPET IN AUDITORIUM AT RGNUL
CAMPUS, SIDHUWAL ON PATIALA BHADSON
ROAD, PATIALA
VOLUME – II**



(Construction and Maintenance Wing)
Rajiv Gandhi National University of Law, Punjab, Patiala
Documents framed & submitted by:-

ARCHITECT / CONSULTANTS:

M/s Kothari Associates Pvt. Ltd.

G – 65, Connaught Circus, New Delhi 110001
011 23325040, 011 23324598, Fax: 011 23712001

DNIT is recommended for Approval please.

University Engineer

Technical Advisor (Civil)

DNIT Approved

Technical Advisor (Civil)



RGNUL, PUNJAB

(Construction and Maintenance Wing)

TENDER DOCUMENT

TENDER NO.	~ RGNUL/CMW/ 09
NAME OF WORK	~ PROVIDING & FIXING OF THE CUT PILE DESIGNED CARPET IN AUDITORIUM AT RGNUL CAMPUS, SIDHUWAL ON PATIALA BHADSON ROAD, PATIALA
TIME LIMIT	~ 01 MONTHS
EARNEST MONEY	~ Rs 25,000/-
LAST DATE AND TIME OF RECEIPT OF TENDERS	~ 08/08/2016 (UPTO 11:00 A.M.)
DATE AND TIME OF OPENING OF TENDERS (TECHNICAL BID)	~ 09/08/2016 (AT 11:30 A.M.)
COST OF TENDER	~ Rs. 5,000/-
PROCESSING FEE	~ RS. 2300/-
DATE AND TIME OF OPENING OF TENDERS (FINANCIAL BID)	~ 11/08/2016 (AT 11:00 A.M.)

**PROVIDING & FIXING OF THE CUT PILE DESIGNED CARPET IN AUDITORIUM AT RGNUL
CAMPUS, SIDHUWAL ON PATIALA BHADSON ROAD, PATIALA**

S.No	DESCRIPTION OF ITEM	Appx quantity.	UNIT	Rate to be quoted by the bidders	Amount
1	Providing and laying of cut pile designed carpet over the specified area with following specifications. The floor which receives the carpet to be thoroughly cleaned as per manufacturer's specifications. Before laying of the carpet, the executing agency will level the surface with plaster of paris wherever required. The carpet is to be laid over a bed of manufacturer's approved adhesive spread evenly over the entire floor. The rate shall include cutting, trimming, fixing and clearing away of residual material to a location as directed. The laid carpet to be vacuumed after the removal of protective cover/on commissioning. If after the protective layer is removed and stains observed in the carpet because of inadequate protection, the same shall be shampooed and made good to the satisfaction of the project managers. The measurements of carpet will be the actual laid area.	1245	SQM		
	Providing & laying carpet with following specifications:				
a	Construction - cut pile wilton weave				
b	Fiber - 2 ply twisted yarn pp				
c	Pile wt - 1100 grams / meter				
d	Pile ht - 5 to 6mm				
e	Color fastness - As per international standards				
2	Providing & laying of EPE foam 8mm thick, underlay carpet in the aisles and gangway.	350	SQM		
	TOTAL				
	General Note :				
1	Scope - Work shall include the furnishing of all materials, equipment and labour to install the complete Carpet system with the manufacturer's approved adhesive.				
2	It is the Vendor's / supplier's responsibility to ensure that materials delivered on site is on the decided date by the project team & it is safeguarded from the time of his purchase until he hands over the finished flooring. It is desirable to store materials in a pre decided flat, clean and dry surface.				
3	Carpet floor shall be installed by a thoroughly experienced vendor and the type of installation shall be as per manufacturer's specifications. The Vendor shall inspect the premises prior to commencement of work and verify that the building is ready for installation.				
4	Carpets to be laid as per the pattern indicated on drawing. All octroi ,freight & handling to be accounted for and no additional amount shall be paid for the same. Rate to be inclusive of covering of carpet with 125 micron single layer plastic cover & sealing of joints with tape. Any pencil marks etc., shall be removed using ordinary pencil eraser. All damaged portions to be replaced free of cost.				
5	It is the Vendor's / supplier's responsibility to check the area of the each type of flooring material before placing the order.				
6	Areas like partitions thickness or columns that is not carpeted shall not be included in the payable costs.				

CONTRACTOR/CONTRACTING AGENCY

WITNESS

REGISTRAR

7	Executing agency will use maximum & full width of the carpet in most the areas, less width shall only be allowed, where there is not practically possible as per site requirements. In such areas the pattern of the carpet should match the adjoining carpet area without fail. Continuation of the pattern should not be disturbed in any case. Area not matching with the continuous pattern will be got re laid without any extra cost.
8	Executing agency will ensure that, the entire carpet is of the same lot / color.
9	The agency shall cut the carpet for accomadating foot lights or any other appliances wherever required without any additional cost.